BANGALORE DIVISION.

Dated 8th July 1908.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 27th July 1908, for constructing a combined building for the Central Police Station and District Superintendent's Office at Fort, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1909.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing combined building for the Central Police Station and District Superintendent's Office, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for a combined building for the Central Police Station and District Superintendent's Office at Bangalore.

No.	Items of work	Per	Ground floor	Upper floor	Lock-up and compound	Miscellaneous	Total
			Quantity	Quantity	Quantity	Quantity	Quantity
1	Earth work excavating foundation and filling in ...	C. yds.	688	...	283	...	971
2	Concrete foundations	C. ft.	4,364	...	1,936	...	6,300
3	Burnt stone in chunam filling foundation with old stones	,,	9,018	...	3,018	...	12,066
4	Burnt stone in chunnam basement	,,	1,797	...	1,156	...	2,953
5	Burnt brick in chunnam superstructure	,,	6,804	...	4,697	...	11,501
6	Do do	,,	...	4,725	...	...	4,726
7	Do arch work	,,	765	...	19	...	784
8	Do do	,,	...	117	...	...	117
9	Burnt stone slabs moderately dressed	S. ft.	491	...	275	...	766
10	Do do	,,	...	411	...	...	411
11	Plastering with chunnam	Sqr.	85·67	...	62·20	...	147·87
12	Do do	,,	...	68·32	...	...	68·32
13	White and color washing	,,	85·67	...	62·20	...	147·87
14	Do do	,,	...	68·32	...	...	68·32
15	Pointing with chunnam	,,	4·39	...	5·42	...	9·81
1	Rolled steel girders	Cwt.	15·00	23·00	2 91	...	40·91
17	Reinforced concrete slabs	S. ft.	20·71	..	1,344	...	3,415
18	Do do	,,	...	2,500	...	...	2,500

81

No.	Items of work	Per	Ground floor	Upper floor	Lock-up and compound	Miscellaneous	Total
			Quantity	Quantity	Quantity	Quantity	Quantity
19	Reinforced concrete pillars with bases and capitals complete	C. ft.	...	...	27	...	27
20	Do do	,,	...	63	...	...	63
21	Teak wood doors ¾th panelled both sides and ¼th glazed with glass fanlight above including hinges, bolts, locks and iron hold fasts etc., complete	S. ft.	278	...	...	...	278
22	Do do without fanlight	,,	...	160	...	...	160
23	Teak wood windows outside panelled, inside glazed fanlights above with iron bars etc, complete	,,	485	...	...	...	485
24	Do do	,,	...	96	...	...	96
25	Do do without fanlights	,,	...	289	...	...	289
26	Teak wood glazed ventilators	,,	...	74	...	...	74
27	Teak wood doors with iron barred shutters including painting	,,	...	...	72	...	72
28	Teak wood batten window with iron bars including painting	,,	...	...	10	...	10
29	Teak wood ventilators with iron bars and perforated zinc sheet including painting	,,	...	...	38	...	38
30	Painting doors and windows	Sqr.	17·61	...	...	...	17·61
31	Do do	,,	...	15·10	...	...	15·10
32	Parapet wall with pillasters and etc., complete 2½' height and ¾' thick	R. ft.	...	150	..	...	150
33	Parapet wall with pillasters and etc., complete 1½' hight and ¾' thick	,,	...	169	...	...	169
34	Do do do	,,	...	..	218	...	218
35	Cornice walls alround the building 1½ feet deep	,,	221	...		...	221
36	Do do	,,	...	315	..	...	315
37	Do 9" deep	,,	...	...	198	...	198
38	String course or light cornice	,,	173	...	...	...	173
39	Do do	,,	...	66	...	...	66
40	Flooring with Cudapah slabs over 3" concrete and cement pointing	Sqr.	18·17	..	9·78	..	27·95
41	Cast iron railings	R. ft.	...	63	...	...	63
42	Teak wood stair case with ornamental cast iron railings	No.	1	...	...	...	1
43	Armouring girders with concrete	L. S.	L. S.	L. S.	L. S.	...	...
44	Coping with brick in chunnam including plastering	R. ft.	...	...	55	...	55
45	Gravelling the open yard between main building and Lock up	C. yds.	...	...	26	...	26
46	Down pipes	L. S.	...	L. S.	L. S.	...	...
47	Drains alround the building	R. ft.	...	...	..	320	320
48	Clearing site after dismantling the old building, levelling ground and forming approach roads etc., complete	L. S.	...	...	...	L. S.	...
49	Compound wall with gate pillars and gate etc., complete (two sides and rear)	,,	...	...	...	L. S.	...
50	Constructing latrines	,,	...	...	...	,,	...

B. S. VENKATACHAR,
Executive Engineer.

KADUR DIVISION.

Notice.

The attention of the public is invited to the notification in this *Gazette*, dated 9th July 1908, calling for tenders for Improving the Ramanahalli Channel, in Chikmagalur Taluk.

R S. NAVARATHNA,
Exec. Engineer.

2 K